

Haus der Berliner Festspiele, Berlin

2010

The complete dismantling and renovation of the stage technical installation with new galleries and lamel grid floor in the stage tower. Over 80 controllable winches, such as SynchroDisks and SynchroPoints. Furthermore, a new orchestra pit lift in three parts. In the far end and backstage area's new lineshaft winches were installed to accommodate temporary storage of sceneries. The existing iron curtain and two stage doors where updated with a new drive system.

Implemented Products

SynchroDisk, SynchroPoints
TNM Control System
Regenerative Power Distribution

Venue Info

Haus der Berliner Festspiele, Schaperstrasse 24,
Berlin

Realisation

Award June 2010, Start Installation June 2010
First Show October 2010

